


ASPHALT IS APPLIED UNIFORMLY TO EACH
PLY AT EVT, AT A RATE OF 25 LBS
PER 100 SQ/FT OF ROOF SURFACE (±15%)



NOTES:

1. REFER TO FIRESTONE WEBSITE FOR MOST CURRENT INFORMATION AT firestonebpco.com.
2. THIS DETAIL MUST BE USED WHERE THERE IS ANY POSSIBILITY THAT DIFFERENTIAL MOVEMENT WILL OCCUR BETWEEN THE DECK AND A VERTICAL SURFACE. THE WOOD MEMBERS MUST NOT BE FASTENED TO THE WALL.
3. JOINTS IN SHEET METAL COUNTERFLASHING MUST NOT BE SOLDERED OR FASTENED.
4. ATTACH WOOD NAILERS WITH SUITABLE FASTENERS.
5. THIS DETAIL MAY NOT BE APPLICABLE FOR USE WITH LIGHTWEIGHT FILLS.
6. ALL SHEET METAL IS TO BE INSTALLED PER SMACNA GUIDELINES.
7. GRANULES MUST BE EMBEDDED WHEN USING TORCH APPLIED GRANULE SURFACED CAP SHEETS PRIOR TO COMPLETING SIDE LAPS, END LAPS, AND BASE FLASHING LAPS.
8. FLASHING LAPS MUST BE OFFSET FROM FIELD LAPS A MINIMUM OF 12" (305 mm).

MAXIMUM WARRANTY: 20 YEARS