


ASPHALT IS APPLIED UNIFORMLY TO EACH PLY AT A RATE OF APPROXIMATELY 25 LBS PER 100 SQ/FT OF ROOF SURFACE (±15%)



NOTES:

1. REFER TO FIRESTONE WEBSITE FOR MOST CURRENT INFORMATION.
2. THIS DETAIL ALLOWS FOR BUILDING MOVEMENT IN BOTH DIRECTIONS.
3. FLASHING REQUIREMENTS TYPICAL FOR BOTH SIDES OF EXPANSION JOINT.
4. ALL SHEET METAL TO BE INSTALLED PER SMACNA GUIDELINES.
5. GRANULES MUST BE EMBEDDED WHEN USING TORCH APPLIED GRANULE SURFACED CAP SHEETS PRIOR TO COMPLETING SIDE LAPS, END LAPS, AND BASE FLASHING LAPS.
6. ATTACH WOOD NAILERS WITH SUITABLE FASTENERS
7. FLASHING LAPS MUST BE OFFSET FROM FIELD LAPS 12" (305mm) MIN.

MAXIMUM WARRANTY: 20 YEARS

Firestone
BUILDING PRODUCTS
NOBODY COVERS YOU BETTER.™
www.firestonebpco.com

EXPANSION JOINT WITH METAL COVER

ASPHALT SYSTEMS

ACCEPTABLE SYSTEMS: BUR

ISSUE/REVISION
DATE:

1/1/2006

NOT TO SCALE

DETAIL NO.

BU-E-1