


ASPHALT IS APPLIED UNIFORMLY TO EACH  
PLY AT EVT, AT A RATE OF 25 LBS  
**PER 100 SQ/FT OF ROOF SURFACE (±15%)**

- NOTES:
1. REFER TO FIRESTONE WEBSITE FOR MOST CURRENT INFORMATION AT [firestonebpco.com](http://firestonebpco.com).
  2. WOOD NAILER MUST BE INSTALLED TO MEET APPLICABLE BUILDING CODES OR 200 LBS PER LINEAR FOOT MINIMUM IN ANY GIVEN DIRECTION.
  3. ATTACH WOOD NAILERS WITH SUITABLE FASTENERS.
  4. THIS DETAIL SHOULD BE USED ONLY WHERE THE DECK IS SUPPORTED BY THE OUTSIDE WALL.
  5. ALL SHEET METAL IS TO BE INSTALLED PER SMACNA GUIDELINES.
  6. COVER EXPOSED PORTIONS OF METAL FLANGE WITH FLASHING MATERIAL.



MAXIMUM WARRANTY: 20 YEARS

**Firestone**  
BUILDING PRODUCTS  
NOBODY COVERS YOU BETTER.™  
[www.firestonebpco.com](http://www.firestonebpco.com)

GUTTER W/O FLANGE USING UNA-EDGE DE & STRIP IN

ASPHALT SYSTEMS

ACCEPTABLE SYSTEMS: BUR

ISSUE/REVISION  
DATE:

01/17/2014

NOT TO SCALE

DETAIL NO.

**BU-RE-2A**